Abstract estimate for constructing a Town Hall at Kortagere, Madhugiri Taluk.

Item No.	Description of work	No.	Rate	Contents	Total
			Rs. a. p.		Rs.
1	Earthwork excavating foundations	C.yd.	0 2 6	14	
1(a)	Filling in up to basement with sand, etc., complete	,,	0 3 0	22	
2	Burnt stone jelly concerte in lime mortar ..	C.ft.	0 3 6	83	
3	Size stone in mortar for foundation ..	,,	0 4 0	578	
4	Burnt brick in mortar	,,	0 4 0	826	
5	Burnt stone slabs 5″ to 6″ dressed and fixed ..	S.ft.	0 5 0	162½	
6	Teak wood doors with 4″×5″ frame 1½″ panelled shutters including two coats of varnish, ⅔ glazed	,,	2 0 0	28	
6(a)	Do windows	,,	1 12 0	180	
7	Semi-circular arch over doors as per design ..	Each	15 0 0	1	
8	Flooring with cement concrete 3″ including plastering with coloured cement cut line, etc.	Sqr.	20 0 0	3.96	
9	Pillars in front verandah with wire cut bricks in cement mortar 1⅛ dia.	Each	15 0 0	2	
10	Rolled steel girders of Tata's 10″×5″ including fixing and hoisting	Cwt.	20 0 0	12.8	
11	Boxing for rolled steel joists	R.ft.	0 8 0	10	
12	R.B.C. roofing as per specification	Sqr.	65 0 0	6.24	
13	Chunam plastering	,,	3 0 0	19.82	
14	White washing, 2 coats	,,	0 4 0	19.82	
15	Parapet wall with burnt brick in mortar 1½′ high and 9″ thick including plastering with blocking course 6″ high	R.ft.	0 10 0	66	
16	Painting doors with green paint, 2 coats ..	Sqr.	4 8 0	4.16	
17	Zinc sheet down water pipes, 4″ dia. including fitting, etc.	R.ft.	0 4 0	48	
18	R.C. Chajja work projection 3″ thick ..	S.ft.	0 8 0	104	
19	Cement pointing to basement	Sqr.	3 0 0	1.43	
20	Preparing and inserting teakwood almirah with its fitting	Each	60 0 0	2	
21	Do teakwood shelves in the hall ..	L. S.	60 0 0	..	

P. RAJAGOPALAN,
Executive Engineer.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Abstract Notification dated 15th July 1940.

The attention of the public is invited to the notification calling for tenders for taking over the stair case room in the Public Office, Mysore, for running Coffee Club for one year from 21st September 1940, published in page 1733, Part VI of the *Mysore Gazette*, dated 25th July 1940. The last date for receiving tenders is 21st August 1940, till 12 NOON. The earnest money to be deposited is Rs. 20.

Notification dated 11th August 1940.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 2 P.M., on 31st August 1940, for constructing a building for extending the University office building, Mysore (adding a Council Hall).

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of four annas only for each form, should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for extending the University office building, Mysore (adding a Council Hall.)". The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 1,023 only in cash as earnest money The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest.) The amount of earnest money should be paid direct to the treasury and the duplicate treasury chellan submitted separately along with the tender.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 26th August 1940 at 4 P.M. The final acceptance of the tender will rest with the Superintending Engineer who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Assistant Engineer, Headquarter Range, Mysore, on all working days, between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Assistant Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department within six months from the date of intimation of the approval of the tender, failing which the Assistant Engineer may, at his discretion, levy a penalty up to Rs. 10 per day of delay which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the Assistant Engineer in the interest of the work, shall be accepted by the tenderer at the rates fixed by the Assistant Engineer and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note—(*a*) The contractor should at his own cost—

(1) Provide, rods, stakes, ropes and labours required to setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water cisterns, water-shoots, coverings to masonry, tile pieces to steps, sieves, parahs, or measures, shoring and other requisite protection during the progress of the work.

(6) Supply all water required for work and workmen and shall provide latrines, drainages, etc.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling from excavations and foundations, wherever and whenever necessary with their own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.

(10) Afford facilities to any other parties employed upon the work so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(*b*) It is the business of the contractors to make their own arrangements for the quarries and supplies of materials.

23. The rates for woodwork for all works quoted should be based on the rates of the departmental supply as noted below. Only Mysore teak selected from the Mysore Government Depots must be used.

24. Work to the extent of Rs. 5,000 will have to be carried out each month.

25. Only Chamundi Brand cement should be used for all works requiring this nature.

26. Such of the tenders which do not clearly quote with detailed specifications for all the items without exception will not be considered.

Abstract estimate for adding a Council Hall to the University Office at Mysore.

No.	Items of work	Unit	Rate	Quantity	Cost
	Ground Floor.	—	Rs. a. p.		Rs.
1	Earthwork excavation for foundation and filling in basement	C.yd.	0 4 0	215	54
2	Filling in foundation with granite jelly concrete in lime mortar	C.ft.	0 3 6	1,671	366
3.	Size stone in chunam for foundation—including bond slabs	,,	0 5 0	3,092	966
3*a*	Size stone in lime mortar for basement including bond slabs all joints neatly dressed at corners for a width of 2″	,,	0 6 0	1,569	588
4	Burnt brick in chunam for superstructure with bond slabs, etc., complete	,,	0 4 0	4,886	1,222
5	Burnt brick in lime mortar arch work ..	,,	0 6 0	191	72
6	R.C.C. slabs over doors and windows with proper reinforcement	,,	2 8 0	107	268
6*a*	Cement concrete slabs 1 : 2 : 4	,,	0 12 0	237	178
7	Burnt stone slabs with two lines dressing on exposed faces and one line dressed on other faces and fixed in mortar bed	S.ft.	0 10 0	550	344
8	Constructing brick in cement mortar pillars with base, etc., as per design including plastering complete ($2\frac{1}{2}' \times 1\frac{1}{2}' \times 15$)	No.	35 0 0	6	210
9	Providing and fixing teakwood doors 4″ × 5″ frames and $1\frac{1}{2}$″ thick panelled shutters with pin headed glass rectangular ventilators on top including copper oxidised brass fittings rim locks with handles, finger plate, etc., complete including latches, etc.	S.ft.	2 8 0	273	680
10	Providing and fixing teakwood windows with frames $3\frac{1}{2}'' \times 4\frac{1}{2}''$ and shutters $1\frac{1}{4}''$ thick $\frac{1}{2}$ panelled and $\frac{1}{2}$ glazed with pin headed glass and top rectangular glazed ventilators with copper oxidised brass fittings and $\frac{3}{4}$″ iron bars, etc., complete ..	,,	2 12 0	558	1,534
11	Providing and fixing reinforced cement fret work ventilators of approved design	,,	1 0 0	65	65
12	Providing, hoisting and fixing R. S. girders of B. S. S. tested including one coat of anticorrosive paint boxing with terrace bricks in cement mortar including plastering complete	Cwt.	18 0 0	84.4	1,519

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
13	Roofing with R. C. C. terrace as per standard specifications including bottom plastering and floor finishing at top, etc., complete	Sqr.	72 0 0	24.40	1,757
13a	Coving the ceiling with offsets	R.ft.	0 8 0	352	176
14	Flooring with 1½″ cement concrete over 3″ chunam concrete ½″ cement plastering including colouring and cutting borders, etc., complete	Sqr.	18 0 0	20.21	364
15	Chunam plastering smooth	,,	3 0 0	92.72	278
15a	White and colour washing	,,	0 5 0	102.00	32
15b	Polishing doors and windows (lac polish)	,,	7 0 0	11.72	82
15c	Painting with lac factory green, two coats	,,	4 8 0	8.37	37
16	Providing R. C. C. chajja with anchorage in walls plastering top and bottom end cornice, etc., complete as per specification	S.ft.	0 12 0	295	221
17	Cement skirting to walls 9″ high and beading at top, etc., complete	R.ft.	0 3 0	317	59
18	Constructing parapet wall with burnt brick in mortar and plastered over as per design, etc., complete ..	,,	1 0 0	28	28
	First Floor.				
1	Burnt brick in lime mortar for superstructure ..	C.ft.	0 4 3	3,104	821
2	Brick in composite mortar pillars (2½×1½×12′) ..	No.	25 0 0	4	100
3	Providing and fixing teakwood doors 4″×5″ and 1½″ thick shutters with ½ panelled and ½ glazed with pin-headed glass copper oxidized fittings with rim locks, finger plates, etc., complete including catches	Sqr.	2 8 0	76	190
4	Providing and fixing teakwood windows with 3½″×4½″ frames 1½″ thick shutters fully glazed with pin-headed glass top rectangular ventilators and copper oxidised fittings, etc., complete with ¾″ iron bars ..	S.ft.	2 12 0	696	1,914
5	R. C. C. slabs over doors, windows, etc., complete ..	C.ft.	2 8 0	50	125
6	Providing, hoisting and fixing R. S. girders of B. S. S. including one coat of anticorrosive paint and boxing, etc., complete as per specifications ..	Cwt.	19 0 0	64.3	1,221
7	Cement concrete slabs for wall plates and cills of windows 1 : 2 : 4	C.ft.	0 12 0	110	83
8	Polishing doors and windows 2 coats with lac polish ..	Sqr.	7 0 0	10.00	70
9	Painting with 2 coats of laboratory green for exterior of windows	,,	4 8 0	8.96	40
10	Skirting with cement including colouring and beading at top, etc., complete	R.ft.	0 3 0	303	57
11	Roofing with R. B. C. terrace as per standard specification including top and ceiling plastered ..	Sqr.	70 0 0	22.73	159
12	Cement concrete chajja with proper reinforcement and anchoring into wall top and bottom plastered and end cornice, etc., complete as per specifications.	S.ft.	1 0 0	753	753
13	Parapet wall with burnt brick in mortar chunam plastering white and colour washing as per design	R.ft.	1 0 0	210	210
14	Chunam plastering smooth	Sqr.	3 4 0	65.45	212
15	White and colour washing	,,	0 5 6	72.00	25
16	Providing and fixing cast iron rain water pipes with heds bend, etc., complete	R.ft.	1 8 0	300	450
17	Providing and fixing teakwood staircase with turned ballustrades railings, etc., complete as per design.	S.ft.	3 4 0	152	494
18	Teakwood turned ballustrades railings alround well hole of stair-case as per design	R.ft.	2 12 0	20	55
19	Providing teakwood dias with steps, etc., on teakwood frame work including wood oiling ..	S.ft.	2 0 0	448	896
20	Coving the ceiling with 3 offsets	R.ft.	0 8 0	303	152

Notification dated the 13th August 1940.

Applications in sealed covers for running an Indian Restaurant for one year from 15th September 1940 in the Exhibition Grounds, Mysore, will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 2 P.M. on the 31st August 1940.

Each application must be accompanied by a deposit of Rs. 100 in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for due fulfilment of contract. (Cash amount will not carry interest). The amount of the earnest money will be paid direct to the treasury to the credit of "17 (*a*) P. W. Deposits" and the treasury duplicate challan submitted separately along with the application or tender.

A schedule of rates of various kinds of refreshments and meals should accompany each application.

The application should state the highest amount that they are prepared to pay for running the Restaurant in the Exhibition Grounds for one year.

The final acceptance of the tender or application will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reasons whatever for the rejection of any.

The name of the successful applicant or tenderer will be posted on the Notice Board in the Assistant Engineer's Office. Within three days of the acceptance of the application or tender, the successful tenderer will be required to execute the agreement in the prescribed form agreeing also that he would sell wholesome food stuff prepared in unadulterated ghee at the rates approved by the Department.

Failure to comply with the above condition or to agree to run the Restaurant in accordance with the instructions of the Department will entail forfeiture of earnest money.

The successful applicant should also abide by the instructions of the Department regarding the keeping the place neat and payment of rent in advance each month.

The premises allotted for the Restaurant may be inspected by the intending tenderers before sending their applications.

N. NARASIMHA IYENGAR,
Assistant Engineer.

KRISHNARAJ SAGAR DIVISION, KRISHNARAJ SAGAR.

Abstract Notification dated 3rd August 1940.

Subject:—CONSTRUCTING AMILDAR'S QUARTERS AT KRISHNARAJNAGAR.

Attention of the public is invited to notification calling for tenders for the above work on pages 1772-1774, Part VI of the *Mysore Gazette*, dated 1st August 1940.

2. The tenders will be received by the Executive Engineer, Krishnaraj Sagar Division, Krishnaraj Sagar, up to 2 P.M. of 31st August 1940.

3. An earnest money of Rs. 350 should accompany the tender.

4. The tenders will be opened in the presence of such tenderers, who wish to be present, on 31st August 1940 at Krishnaraj Sagar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1941, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

BATNI BHIMA RAO,
Executive Engineer.

HASSAN DIVISION.

Notification dated 13th August 1940.

Sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, Hassan, up to 27th August 1940 till 3 P.M. for constructing a Police Station Building at Banavar, Arsikere Taluk.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Hassan Division, Hassan, should be addressed to the Executive Engineer, Hassan Division, Hassan, and should be superscribed as "Tender for constructing a Police Station at Banavar, Arsikere Taluk." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 285 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest.) In case of the acceptance of the tender, an addition of the five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department Form.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date of opening. The final acceptance of the tender will rest with the ..... Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.